

**EAUC Sust Construction TSN 29 April 2015**

**PASSIVHAUS RETROFITS IN ZURICH AND GRAZ**  
**Lessons for Scotland**

Prof Colin Porteous  
Mackintosh Environmental Architecture Research Unit (MEARU)  
Mackintosh School of Architecture, The Glasgow School of Art

IEA ECBCS Annex 50  
Prefabricated Systems for Low Energy  
Renovation of Residential Buildings

# Building Renovation Case Studies

IEA ECBCS Annex 50  
Prefabricated Systems for Low Energy  
Renovation of Residential Buildings

# Building Renovation Case Studies

March 2011



International Energy Agency  
Energy Conservation in  
Buildings and Community  
Systems Programme





## Renovation concept



Figure 5: View of renovated building

### Design data of renovated building

Year of renovation	2009-10
Measurement period	July 2010-June 2011
Number of apartments	6
Heated floor area	657 m <sup>2</sup>
Total heating energy (incl. hot water)	13,257 kWh/y
Spec. energy consumption	20 kWh/(m <sup>2</sup> ·y)
Heating energy savings (per m <sup>2</sup> )	88.6%
PV electricity gains	17,983 kWh/y
Rents (net)	120,000 €/y
Additional cost	3,000 €/y
Rent increase	39%

### Key points of renovation

Maximization of living surfaces with the construction of a new attic apartment and an extension of the ground floors.

Renovation of the building envelope in Minergie-P standard (Passive House standard), with preservation of the architectural quality.

Substitution and installation of new building technologies systems: new heating system, but keeping the old radiators, new ventilation system, new hot domestic water system, and new electric installations.

Use of renewable energy: ground source heat-pump, solar collectors, and horizontal PV-system on the roof.

Inner refurbishment: new bathrooms and kitchens

Refurbishment with taking care to recycle existing structures and materials, in order to minimize the consumption of grey energy.




Figure 6: Floor plan of added penthouse apartment




Figure 7: Floor plan showing the changes of the renovated building




Figure 6: Floor plan of added penthouse apartment




Figure 7: Floor plan showing the changes of the renovated building

## Renovation design details

### Façade solutions

The construction of the prefabricated large façade modules was a challenge. First measurements were taken by the University of Applied Sciences of North-Western Switzerland and by laser-measurements of the existing façades. The goal was to produce the elements based on this data. Because of difficulties to configure the data of the geometer to the needs of the architect, the contractor took also own measures. The new, large scale elements in timber construction had to fit on the imprecise and curved old walls. Because of this difficulty, cellulose insulation was used in order to fill all the gaps. The connections between the new windows and the old walls was covered by plasterboard and tightened by sealing tapes. The air-tightness of the renovated structure is excellent.




Figure 8: Horizontal section of façade element with integrated ventilation ducts

#### Wall construction

U-value: 0,	18 W/(m <sup>2</sup> ·K)	Prefabricated element:	
Interior rendering	10 mm	Tolerance / thermal insulation	
Brick wall	320 mm	(cellulose)	20 mm
Exterior rendering	20 mm	Insulation (cellulose)	180 mm
		Wood fibre board	40 mm
		Exterior rendering	10 mm
		Total (incl. existing wall)	600 mm




Figure 9: Vertical section with horizontal ventilation distribution




Figure 10: Vertical section of living room extension

### Roof solutions




Figure 11: Vertical section of building. New parts in red (new balconies to the South, additional penthouse apartment, building annex for new heating system)

#### Roof construction

U-value: 0,	11 W/(m <sup>2</sup> ·K)
Three-layer slab	27 mm
Thermal insulation	360 mm
Three-layer slab	27 mm
Air space /	
Three-layer slab	200 mm
Polymer bitumen seal	10 mm
Recycled rubber mat	7 mm
Substrate geo-membrane	60 mm
Total	691 mm

## From the 50's to the future

### Net zero energy renovation of a Swiss apartment building in Zurich

**Owners:** Peter Rieben, Markus und Sara Rieben, Zürich  
**Architect:** kämpfen für architektur, Zürich  
**Energy concept:** René Naef, Zürich  
**Report:** Nadja Gritschott  
**Location:** Zürich, Switzerland  
**Renovation:** 2009-2010

#### Key technologies

- Large prefabricated wooden elements
- Façade integrated ventilation system
- Ground-source heat-pump with 260 m deep bore holes
- 12.5 m<sup>2</sup> vacuum solar collectors
- 16.1 kWp PV-system



## Construction process



Figure 18: The on-site preparation is done by leveling laths. In-between the distribution system and supply pipes are installed.



Figure 19: The solar collectors were integrated into the prefabricated modules.  
(Source: Gap-Solution GmbH)



The renovation proceeded very smoothly :


The on-site preparation comprised the installation of the levelling laths, where in-between the heat distribution panels and supply lines were mounted. Afterwards the remaining space was filled with rock-wool. The modules were brought by a low-loader to the building site, lifted by a truck-mounted crane to the facade. Additionally on each side two assembly operators supported the fitting procedure. After the entire facade was covered with the new modules the old windows were removed from the inside, the vapour barriers were sealed (building angles, window-reveal,...) and the collectors were connected to the supply pipes.



Figures 20-22: Sequence of assembly of the modules on the south-oriented facade  
(Source: Gap-Solution GmbH)








# Solar 'honeycomb' detail: Architekturburo Hohensinn, 2007-2010

## Renovation design details

### Façade solutions



### Layer composition of basic facade module

Existing wall	10 mm	Internal plaster
	300 mm	Existing exterior wall
	25 mm	External plaster
On-site installation	100 mm	Levelling laths In-between rock-wool
Pre-fabricated module	18 mm	OSB-board
	120 mm	Timber frame between rock wool
	15 mm	MDF- board
	30 mm	Solar comb
	29 mm	Rear ventilation
	6 mm	Toughened safety glass

Figure 7: Pre-fabricated façade module

- 'On-site installation' includes heating serpentine embedded in XPS board on face of original wall; principle by Austrian Architect, Walter Unterrainer, cold U-value 0.2 falls to 0.13 W/m<sup>2</sup>K mean, and often below zero; predicted heat demand 12 kWh/m<sup>2</sup> annually, i.e. 3 kWh/m<sup>2</sup> below PassivHaus standard.







