





CSE: IWS & Börse Frankfurt: IWI

FEB - 2016



Agenda







- Project Background
- Relationships and Contracts
- Economics

https://youtu.be/DATn4kjzxEo

- Technical
- Marketing Project Launch and Social Benefits
- Opportunity & Challenges



2



Project Background









- SHARC Energy Systems Business launched June 2014.
- Introduced to college by Scottish Water in July 2014
- College GHG emissions challenge ongoing following
 - Energy efficiency retrofit
 - Solar installation
 - Looking for a renewable heat source
- Competitor Biomass boilers
- SHARC Feasibility completed August 2014 demonstrated
 - Similar GHG savings to biomass
 - Saved on fuel delivery
 - Stabilised heat price
 - No up front capital
- Commenced contract negotiations November 2014
- Started works June 2015.





Project Relationships and Contracts



Green Investment Bank



- SPV established (SHARC Caledonia)
 - 60/40 JV between GIB/Equitix and SHARC
- JV to Borders College Ultimate client and consumer of heat
 - 20 year Heat Purchase agreement (aligned to UK Government RHI timeline).
 - License to occupy allowing SHARC asset to occupy college land for 20 years.
- JV to Scottish Water Provider of resource and lead generator
 - Use of Sewer contract
 - Carries a "Technical payment" related to capex value (commission)
 - Ongoing annual rental (Gate fee) related to energy generated PA
- JV to SHARC
 - Shareholder agreement to govern management of SPV
 - Installation contract to cover project
 - O&M contract to cover operation of system for 20 years
- Suit of contracts can be rolled out to any project going forward





Project Drivers









- UK Demonstrator (SHARC)
- Carbon Savings
 - 150 tons of Carbon saved per year (Brown Electricity Calculation)
- Building Comfort levels 1.8GWh's of heat demand per year
 - 95% expected to be delivered by SHARC
 - Supplemental Gas supply to top up in extreme cold
 - Existing Boilers system retained for resilience
- Economics
 - System eligible for RHI
 - Heat sales to college fixed at below gas for 1st 5 years
 - Heat from SHARC at 400% v Gas boiler 85%
- Capex £950,000.00 covered by SHARC
- O&M costs covered by SHARC include
 - Maintenance
 - Electricity
 - SW gate fee





Project Technical









- Pre-contract design
 - Civil Engineering
 - Mechanical & Energy engineering
 - Due Diligence from Equitix TA (WSP)
- Onsite construction of
 - Energy Centre
 - Sewer Interface and Pumping station install
 - 500m of Flow return heat network, connecting 5 plantrooms
 - Plant room adaptation of college heat distribution connection to LLH
- Off site production of equipment for install at site
 - SHARC skid and PHX
 - Heat Pumps
 - Controls software development
 - Pump sets
- Post contract commissioning







SHARC wet well incorporating a penstock into main sewer

The Borders project utilizes the adjacent town Sewer for supply





Construction of the sewer interface



SH/RC ENERGY SYSTEMS

500m low temperature heat network installed



Heat distribution from Energy centre to Network

Pre-Insulated heat network external connection to High Mill







Retrofit Solution to ageing building.



Research/Labs plantroom SHARC pipework interface



SHARC pipe work installation to TTC building



External mains into Research/labs



High Mill Building Occupied by Herriot Watt University

















Project Opportunities









Marketing - The Borders project demonstrates

- The retrofit credentials of system.
- The use of the system in DHN opportunity.
- The tie in to town sewer networks.
- The ability to fund projects under heat supply agreements.

Customer benefits - SHARC Energy will provide the College with

- 1.8 GWh of annual heat
- GHG emissions saving of in excess of 150 tones per year
- 20 year stable heat supply price

Social Benefits

- Regional Employment during construction and operational stage
- Energy Security Locally produced energy supply
- Reduced GHG emissions
- Contribution to local economy
- Opportunity to include small social fund to support adopting customer



Borders College Launch











Project Launch Event 8th December 2015

- 100 + delegates attended
- Event Supported by Scottish Government Minister
- Event Supported by SW main board Director
- Substantial Post event PR and media coverage

Demonstrator credentials of system continue to support on going promotion to market;

- 6 post event demonstration visits
- 1 event involved 40 delegates.







Project Opportunities & Challenges





Performance after first half of operation

- ✓ 150MWh's heat delivered down on estimates due to early Easter break & unseasonal summer weather.
- ✓ Heat delivery to college operating comfortably at 55°C flow (project modeled at 63°C)
- ✓ System COPs consistently above 4.5 (project modeled at 3.7)
- ✓ BMS & retained boiler interface needs some work
- ✓ Monitoring process has identified modifications to improve performance and resilience
- ✓ So far so good!

THANK YOU

For more information please visit our website at www.sharcenergy.com

Or Phone office lines UK +44 115 870 0021 Can +1 604 219 2838

CONTACT

Lynn Mueller – <u>Lynn.mueller@iws-sharc.com</u> P: +1 604-475-7710 Russ Burton – <u>Russell.burton@iws-sharc.com</u> P: +44 7990 550063

International Wastewater Systems

G



CSE: IWS & Börse Frankfurt: IWI